ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Dated 8th April 1925.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. 20th April 1925, for constructing Physics Laboratory attached to Vani Vilas Institute, Bangalore City. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1925.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the working hours.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

3a. The progress to be shown on the 15th June should be specially stated.

4. Each tender must be accompanied by a deposit of Rupees two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Physics Laboratory attached to Vani Vilas Institute" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. In the matter of all disputes about rates, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Chief Engineer will be final and legally binding.

Abstract of quantities for constructing Physics Laboratory attached to Vani Vilas Institute.

No.	Items of work	Quantity	Per
1	Earthwork excavation	207	C.yd.
2	Lime concrete filling foundation	925	Grt.
3	Stone in mortar foundation	2,574	"
4	Do basement	739	"
5	Dressed stone slabs	447	S.ft.
6	Burnt brick in mortar, superstructure	4,471	C.ft.
7	Earthwork filling basement	99	C.yd.
8	Teakwood work wrought and putup	111 3/4	C.ft.
9	Iron trusses complete	28 1/2	Cwt.
10	Teakwood panelled doors with 1½" thick planks iron fastenings complete	1571/2	S.ft.
11	Teakwood windows with ½ panalled and ½ venetianed shutters outside and glazed shutters inside with iron bars, hinges, etc., complete.	189	"
12	Teakwood ventilators with glazed shutters and iron bars	70	"
13	Burnt stone lintels	251	"
14	Roofing with 1st Class Mangalore tiles over teak reepers with wood oiling	20·52	Sqr.
15	Ornamental ridge tiles set in mortar	54	R.ft.
16	Chunnam plastering	60·42	Sqr.
17	Dental cornical round 1 foot	175	R.ft.
18	Flooring with 1½" Cuddapa slabs one 3" concrete bed and cement pointing	13·72	Sqr.
19	White washing two coats	60·42	"
20	Colour washing	25·17	"
21	Removing and refixing windows	3	No.
22	Opening two door ways and fixing two new doors	2	"
23	Burnt brick in mortar and plastering	39	C.ft.
24	Wood oiling two coats	9·40	Sqr.
25	Silicate painting	10·36	"
26	Cement string course	138	R.ft.

R. W. SCALDWELL,
Executive Engineer.